

BACKGROUND

1. The City of Ocala is seeking quotes from contractors to demolish and remove structure, improvements, and structure contents at **1408 NE 17th St, Ocala, FL 34470**.
2. Contractor will provide all labor and equipment to complete this project.
3. Photographs of the structure are attached as **Exhibit B – Photos of Structure**.
4. **MANDATORY SITE VISIT:** Bidders must conduct a site visit at their convenience in order to participate in this bid.

*****MANDATORY REQUIREMENT*******STRUCTURE TO BE ABATED BY A FLORIDA LICENSED ASBESTOS ABATEMENT CONTRACTOR PRIOR TO DEMOLITION**

Only a Florida licensed asbestos contractor using properly trained, certified, and licensed asbestos workers can perform asbestos removal projects in Florida. Air monitoring during and after abatement activities is also recommended to document the fiber levels inside and outside of the abatement work area. Contractor is responsible for disposal of asbestos waste at an approved solid waste disposal facility.

LICENSING AND EXPERIENCE REQUIREMENTS

1. **Licensing Requirement:** Contractors must submit proof that they possess a current, active Asbestos Supervisor license.

The City of Ocala and NESHAP requires an asbestos-trained person be on site. Federal 40 CFR 61.145(c)(8) states in part, "no RACM shall be stripped, removed, or otherwise handled or disturbed at a facility regulated by this section unless at least one on-site representative, such as a foreman or management level person or other authorized person trained in the provisions of this regulation and the means of complying with them is present." DEP requires this "trained person" to be on site when non-friable ACM is present, or is discovered, so problems can be caught early and corrected without delay.
2. **Experience Requirement:** Bidder must possess three 3 years' experience in providing demolition services.

INSURANCE REQUIREMENTS

1. **Commercial General Liability:** with limits of \$1,000,000 per occurrence/\$2,000,000 aggregate.
2. **Commercial Automotive Liability:** a combined limit of not less than \$1,000,000.
3. **Workers' Compensation and Employer's Liability:** per Florida statutory requirements.
4. **Pollution Liability:** for the duration and up to three (3) years after the completion of the project.

PERMIT REQUIREMENTS

1. **City of Ocala Demolition Permit:**
 - A. Contractor must obtain a City of Ocala demolition permit.

- B. If Contractor isn't already "certified" with the City of Ocala, Contractor must complete the Contractor Certification Application prior to applying for a City Demolition Permit.
 - C. The application for demolition permit is available at: <https://www.ocalafl.org/government/city-departments-a-h/growth-management/building/construction-permits>
 - D. It is the responsibility of the Contractor to obtain the approval signatures of the appropriate representatives of the following agencies listed on the City of Ocala Demolition Permit Application: gas, telephone, telecommunication, water and electric utilities, Cox Cable, a licensed exterminator, planning and environmental review from the City of Ocala's Growth Management Department.
2. **Marion County Permits:** In addition to any City required permits, septic tank permits must be obtained from the Marion County Growth Management Services Department, located at 2710 East Silver Springs Boulevard, Ocala, FL 34470. Information regarding septic tank permitting can be obtained by calling the septic permitting office at (352) 438-2417.
3. **Estimated Permit Fees:** The estimated fees and allowance for this project is \$104. Please include this allowance amount in your lump sum bid amount.

PROJECT SUMMARY

This project consists of the following:

- 1. Termination of water and sewer connections at the property line (city meter/sewer laterals) prior to beginning demolition work.
- 2. The asbestos survey is attached below. The contractor shall read it thoroughly and adhere to all DEP asbestos related guidelines while demolishing the structure.
- 3. Demolition and removal of all structures, structural debris, structure contents, improvements, and fencing (FRONT FENCING ONLY) on the property listed above.
- 4. The ground where the buildings are removed will be leveled, and if on a grade, sodded.
- 5. The pool and the concrete surrounding the pool will be abated. The manner in which the pool is abated per the Building Code is summarized as follows: there must be a large hole punched in the bottom that is inspected as part of the Contractor's demolition permit. After passing inspection, Contractor can collapse the pool in on itself and then put the concrete decking into the hole. Contractor can use dirt to fill in the remainder of the hole and grade it in the same manner they grade the rest of the lot.
- 6. Any fuel tanks found must be pumped, disconnected, crushed, and backfilled or pumped and completely removed from the property according to Chapter 62-761 of the Florida Administrative Code.
- 7. Public sidewalks and driveway aprons must remain intact. Any damage to sidewalks or driveway aprons by the Contractor will be repaired at the Contractor's expense.
- 8. Any septic tanks will be pumped, crushed and back-filled, according to City requirements, Florida Building and Plumbing codes, and the Marion County Health Department. Septic Tank Permits must be obtained from the Marion County Growth Management Services Department located at 2710 East Silver Springs Blvd, Ocala. Information regarding septic tank permitting can be obtained by calling the septic permitting office at 352-438-2417.
- 9. Any water wells will be capped according to City requirements and Florida Building and Plumbing codes.

10. Underbrush, overgrowth, fallen trees and all debris must be removed from the property.
11. Property shall be graded to final grade, using a box blade.
12. Weight tickets from the County landfill shall be included with the Contractor's invoice.
13. **DO NOT** remove shed or fence except that portion necessary for demo work.

DEMOLITION TIMEFRAME

1. **Contract Time:** Work must be completed and ready for final payment within **30 days** of the City-issued Notice to Proceed (NTP).
2. **Weather Days:** The Contractor shall submit a written request to the City Project Manager (email is the preferred method) for additional days for which work is suspended or delayed by weather. Weather days shall be reconciled with each monthly pay application for the time period which the application is submitted and shall be final. Contractor performance and execution of work will be considered in the determination for granting additional days.

CONTRACTOR RESPONSIBILITIES

1. Scheduling of demolition shall be coordinated through City of Ocala Community Development Services Christopher Lewis, (352) 629-8333, clewis@ocalafl.org.
2. Contractor shall promptly secure all necessary permits, inspections and approvals required and allow inspection of all work by authorized personnel.
3. No work shall commence until the contractor has submitted proof of #62-257.900(1) - Notice of Demolition* to FDEP and provide proof of mailing to the City Project Manager.
4. Contractor must wait ten (10) business days (excluding holidays as observed by the State of Florida) after the confirmed delivery date, prior to starting demolition. Acceptable forms of proof are as follows:
 - USPS Certified Mail receipt
 - FedEx tracking receipt
 - Similar mailing methods, where delivery date can be verified.
5. *FDEP form 62-257.900(1) - Notice of Demolition is available at the following link: https://floridadep.gov/sites/default/files/dep62_257_900%281%29.pdf
6. The Contractor shall complete all work performed under this contract in accordance with policies and procedures of the City of Ocala and all applicable State and Federal laws, policies, procedures, and guidelines.
7. The Contractor shall obtain and pay for any and licenses, additional equipment, dumping and/or disposal fees, etc., required to fulfill this contract.
8. Contractor shall leave the property at once, without altercation, if advised to leave by law enforcement or a person claiming to be the property owner and/or property owner's representative. Immediately after leaving, contact the City Project Manager and advise them of the situation.
9. Contractor will be responsible for inspector's overtime.
10. Provide on-site sanitary facilities as required by Governing agencies.

11. Contractor is responsible for any and all damages including but not limited to buildings, curbing, pavement, landscaping, or irrigation systems caused by their activity. Should any public or private property be damaged or destroyed, the Contractor, at their expense, shall repair or make restoration as acceptable to the City of destroyed or damaged property within forty-eight (48) hours of notification from the City.

LIQUIDATED DAMAGES

1. The Contractor shall pay the City **\$100.00** for each calendar day that expires after the time specified for completion, until work is completed.
2. Nothing in this section is intended to limit the right to obtain injunctive relief or any and all relief as may be appropriate. Permission allowing the Contractor to continue and finish any part of the work after the time fixed for its completion or after the date to which the time for completion may have been extended shall in no way operate as a waiver on the part of the City of any of its rights under this solicitation.

CONTRACTOR EMPLOYEES AND EQUIPMENT

1. Contractor must utilize competent employees in performing the work. Employees performing the work must be properly licensed or qualified as required by the scope.
2. Contractor must provide a valid telephone number, email, and address to the City Project Manager. The phone must be answered during normal working hours, or voicemail must be available to take a message.
3. At the request of the City, the Contractor must replace any incompetent, unfaithful, abusive, or disorderly person in their employment. The City and the Contractor must each be promptly notified by the other of any complaints received.
4. The employees of the Contractor must wear suitable work clothes and personal protective equipment as defined by OSHA (hard hats, bucket harnesses, etc.) and meeting Manual on Uniform Traffic Control Devices (MUTCD) and National Electrical Safety Code (NESC) requirements as indicated for all work conducted and be as clean and in as good appearance as the job conditions permit.
5. Contractor will operate as an independent contractor and not as an agent, representative, partner or employee of the City of Ocala, and shall control their operations at the work site, and be solely responsible for the acts or omissions of their employees.
6. No smoking is allowed on City property or projects.
7. Contractor shall possess and maintain sufficient equipment to complete the work described herein. Contractor's equipment shall be in good repair, and contractor shall have a qualified operator to maintain the care of the equipment. All operators must be trained in proper use and care of equipment. A list of equipment shall be provided to the City upon request.
8. All company shirts and vehicles must have a visible company name/logo.

SUB-CONTRACTORS

1. Contractor must perform a minimum of **30%** of the work with their own forces.

SAFETY

1. The Contractor is solely responsible for ensuring safety during demolition and for conformance to all applicable OSHA standards; and local, state, and national codes concerning safety provisions for their employees, sub-contractors, all building and site occupants, staff, public, and all persons in or around the work area.
2. Job site visits by City staff do not constitute approval, awareness, or liability for any hazardous condition.
3. Contractor shall be responsible for securing their equipment, materials, clothing, and other property.
4. In no event shall the City be responsible for any damages to any of the Contractor's equipment, materials, property, or clothing lost, damaged, destroyed or stolen.

INVOICING

1. All original invoices will be sent to: Shaneka Greene, Community Programs Division, 201 SE 3rd Street, 2nd Floor, Ocala, FL 34471, email: sgreene@ocalafl.org.
2. Contractor will invoice at least once a month.
3. Weight tickets from a certified landfill must be included with all invoices submitted by Contractor.

PRICING AND AWARD

1. Bids will be received on a lump sum basis and shall include all costs necessary to complete this project (travel costs, permitting fees, disposal, etc.).
2. Award will be made to the lowest bidder meeting all requirements outlined herein.