

Rehabilitation Specification: GRNT 22-0003

Applicant: Tammy Hulon
Address: 1827 NE 28th St
Parcel #: 24393-000-00
Phone: 352-512-3912



Work must comply with the current **Florida Building Code.**

TYPES OF PERMITS REQUIRED:

Building Roofing Plumbing Electrical Mechanical Gas

CONTRACTORS REQUIRED:

General/Builder/Residential Roofing Plumbing Electrical HVAC Gas Specialty

Project must be fully completed in 60 days.

GENERAL CONDITIONS

1. It is the responsibility of the contractor and/or sub-contractors to obtain all required permits necessary to perform the work described above and to properly post/display them clearly at the job site.
2. It is also the responsibility of the contractors and sub-contractors to ensure all required inspections are requested and passed, up to and including the final inspections from the City of Ocala Building Department and the Community Development Services Department.
3. Due to this being an owner-occupied residence, the contractor **MUST** coordinate with the Owner and City of Ocala Building Department/Inspectors when requesting the necessary inspections for this project. (Owner may move out during construction.)
4. All references to equivalent imply the substituted goods/materials must meet or exceed the specifications of the brand requested.

Item 1 – Kitchen cabinets

1. Remove and dispose of all existing backsplash, countertops.
2. Provide and install over the range microwave similar in design and color to existing.
3. Provide and install Formica countertops with 4-inch backsplash, color will be selected by homeowner at contract signing.
4. Install new 8" stainless steel double bowl sink with single lever Delta faucet with sprayer or reinstall owner faucet, includes all related plumbing, water supplies and shut off valves.
5. Repair paint, drywall/backsplash as needed.

Item 2 – Plumbing

1. Install new insulation blanket on water heater.
2. Install water heater discharge pipe to code.
3. Reinstall and secure water heater covers.
4. Install timer for water heater, Intermatic WH40 Water Heater Timer equal or better.
5. Replace pressurized well tank, equal in size or bigger.
6. Remove and reset hall toilet level to the floor.

Item 3 – Electrical

1. Replace GFCI receptacle at pool pump.
2. Check electrical wiring at well and make any repairs to code.

Item 4 – Interior

1. Remove floor coverings throughout except for hall bath.
2. Repair all cracks, holes and soft areas in existing flooring. Install high-density 7/16" or equal padding. Allowance of 320 sf of plywood, 100 lf of 2x8 lumber.
3. Prep floor so that it is clean, dry, and level.
4. Replace carpet with new (max price \$2/s.f.), include transitions where needed.
5. Provide and install if needed shoe molding around full perimeter of flooring.
6. Kitchen/laundry/bathrooms use ceramic tile of similar style, size and type. (max price \$2/s.f.),

Item P – Permits

This amount of __150.00_____ is the estimated permit cost/allowance for this project.

At project closeout and before final payment, Contractor shall submit to homeowner, a 3-ring binder to include:

Prime Contractors information w/warranty

Sub-contractor information

Registered roof warranty and claim information

All owner manuals/instructions

Provide a list of the manufacturer, type, sheen/finish and color of all coatings used and the respective locations where they were applied, to the owner

Color choices (**all color/product choices and/or changes to previously agreed upon choices shall be done in writing**)